

7-28

2-2-0602

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-077-20387-00-00

SE SE NW, SECTION 15 TOWNSHIP 34 RANGE 6W

OPERATOR LICENSE # 4677 2970 FEET FROM S SECTION LINE
2970 FEET FROM E SECTION LINE

OPERATOR Cara Ventures, Inc
NAME & P.O. Box 287
ADDRESS Attica, KS 67009

RECEIVED
KANSAS CORPORATION COMMISSION

LEASE NAME: Albert #1
COUNTY: Harper
WELL TOTAL DEPTH: 4600' ^{49.50}

JUL 30 1993

CONSERVATION DIVISION
WICHITA, KS

CONDUCTOR PIPE: _____
SURFACE CASING: 8-5/8" @ 296'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Pratt Well Service
ADDRESS: P.O. Box 847 Pratt, KS 67124 LICENSE: 5893

COMPANY TO PLUG AT: HOUR: 11:00 DAY: 28 MONTH: 7 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: KCC District #2
COMPANY NAME: Allied Cmt PHONE: 316-793-5861

WERE: Set cast iron plug at 3790', spot 2sx cmt at 3790',
shoot casing at 2500', pull casing to 1050', spot 35sx
at 1050', pull casing to 750', spot 35sx at 750', pull
casing to 346', circulate cmt to surface, pull casing
out of hole and top off with cmt.

PLUGGING PROPOSAL RECEIVED BY: Pual C. Caragianis

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()


COMPLETED: HOUR: 17:00 DAY: 28 MONTH: 7 YEAR: 1993

ACTUAL PLUGGING REPORT:
Set cast iron plug at 3790', spotted 2sx cmt at
3790', shot casing at 1173', spotted 35sx cmt at 1173',
pulled casint to 707', spotted 35sx cmt at 707', pulled
casint to 346', circuated cmt to surface, pulled casing
out of hole and topped off with cmt.
170sx cmt 60/40 4% gel

REMARKS: Allied #2790 Difference in spots due to wrong plg orders

I DID OBSERVE THIS PLUGGING.

INVOICED
DATE AUG 04 1993
INV. NO. 38254



Jerry Clark (AGENT)