

6-24

2-040540

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER: 15-077-21,211-0088  
NW NW NW, SECTION 17 TOWNSHIP 34 RANGE 7W

OPERATOR LICENSE # 30371 4950 FEET FROM S SECTION LINE  
4950 FEET FROM E SECTION LINE

OPERATOR Dublin Petroleum  
NAME & Box 6029  
ADDRESS Enid, OK

LEASE NAME: Harmon #17-1  
COUNTY: Harper

WELL TOTAL DEPTH: 6537' 212.45  
CONDUCTOR PIPE: " @ "  
SURFACE CASING: 8-5/8" @ 237'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SMD  D&A   
OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: TransPac Drilling  
ADDRESS: Great Bend, KS LICENSE: 5929

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Gary Pue  
COMPANY NAME: TransPac Drilling PHONE: \_\_\_\_\_

WERE: 35 sx @ 5350' - 25 sx @ 1400' - 25 sx @ 850' - 25 sx @ 290' - 15 sx @ 60' - 10 sx R.H. - 10 sx M.H.

PLUGGING PROPOSAL RECEIVED BY: Jack Luthi

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 16:00 DAY: 24 MONTH: 6 YEAR: 1990

ACTUAL PLUGGING REPORT:  
The drill pipe was run open-end to top of Arbuckle at 5350' where 35 sx cmt was spotted - drill pipe to 1400', 850' and 290' where 25 sx cmt spotted at each depth - 15 sx cmt circulated from 60' - RH and MH were each circ with 10 sx cmt.

REMARKS: Allied #5593 60/40 6% gel  
I DID NOT OBSERVE THIS PLUGGING.

JUL 9 1990

CONSERVATION DIVISION  
Wichita, Kansas

Steve Van Gieson  
Steve Van Gieson (AGENT)

INVOICED

DATE 7-17-90

INV. NO. 28590

FORM CP-2/3  
REV. 3/90

MK