

9-8

Right  
2-040893

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

DOCKET # D-27,185

API NUMBER: 15-077-21,211-0001

NW NW NW, SECTION 17 TOWNSHIP 34 RANGE 7W

OPERATOR LICENSE # 31160 4950 FEET FROM S SECTION LINE

OPERATOR PHILLIPS EXPLORATION COMPANY 4950 FEET FROM E SECTION LINE

NAME & BROMFIELD CIRCLE

ADDRESS WICHITA, KS 67226

LEASE NAME: HARMON #17-1

COUNTY: HARPER 166.63

WELL TOTAL DEPTH: 5127' PBTD 5016'

PIPE: 5 1/2" @ 5127'

SURFACE CASING: 8 5/8" @ 237'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD X D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE

ADDRESS: CHASE, KS LICENSE: 31529

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MANNY

COMPANY NAME: MIKE'S TESTING & SALVAGE PHONE: \_\_\_\_\_

WERE: PERF 4899' - 4968'

35 SACKS AT 1300'

35 SACKS AT 900'

CIRCULATE 290' TO SURFACE

PLUGGING PROPOSAL RECEIVED BY: DISTRICT II

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (\_\_\_\_\_) PART ( X ) NONE (\_\_\_\_\_)

COMPLETED: HOUR: 16:30 DAY: 8 MONTH: 9 YEAR: 1997

ACTUAL PLUGGING REPORT: THE PERFS WERE COVERED WITH SAND FROM 5016' TO 4750' AND CAPPED WITH 5 SACKS CEMENT. THE 5 1/2" WAS RECOVERED FROM 3800' AND PULLED TO 1300' WHERE 35 SACKS OF CEMENT WAS SPOTTED. PIPE PULLED TO 906' WHERE 35 SACKS OF CEMENT WAS SPOTTED. PIPE PULLED TO 312' WHERE CEMENT WAS CIRCULATED TO SURFACE.

REMARKS: 60/40 POZ 4% GEL COM 3% GEL 2% CACL ALLIED CEMENT

**INVOICED**

DATE 9-11-97

INV. NO. 48977

I DID OBSERVE THIS PLUGGING  
Steve Van Gieson  
STEVE VAN GIESON

RECEIVED  
KANSAS CORPORATION COMMISSION  
SEP 11 1997  
CONSERVATION DIVISION  
WICHITA, KS