

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

12-7

API NUMBER: 15-077-20,851-~~0000~~  
C, NE, SW, SECTION 02 TOWNSHIP 34 RANGE 8W

OPERATOR LICENSE # 5003 1980 FEET FROM S SECTION LINE  
3300 FEET FROM E SECTION LINE  
OPERATOR McCOY PETROLEUM COMPANY  
NAME & 3017 N. CYPRESS  
ADDRESS WICHITA, KS 67226

LEASE NAME: GATES "D" #1 154.70  
COUNTY: HP Hogauer  
WELL TOTAL DEPTH: 4760'

PIPE: NONE

SURFACE CASING: 8 5/8" @ 254'

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE  
ADDRESS: ATTICA, KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: JANA GREEN

COMPANY NAME: McCOY PETROLEUM COMPANY PHONE: 316-  
WERE: 4 1/2" @ 4758', CIBP @ 4430' & 2 SKS. PERFS. 4478-4706'. 35 SX. @  
1350', 35 SX. @ 900', CIRC. CMT. FROM 300', REC. 4050'.


PLUGGING PROPOSAL RECEIVED BY: \_\_\_\_\_

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { X } PART { \_\_\_\_\_ } NONE { \_\_\_\_\_ }

COMPLETED: HOUR: 16:00 DAY: 7 MONTH: 12 YEAR: 1995  
ACTUAL PLUGGING REPORT:

A CIBP WAS SET @ 4430' & CAPPED WITH 2 SX. CMT. 4 1/2" CASING  
RECOVERED FROM 4050'. 4 1/2" CASING PULLED TO 1337' WHERE 35 SX.  
CMT. WAS SPOTTED. PULLED CASING TO 894' WHERE 35 SX. CMT. WAS  
SPOTTED. CASING PULLED TO 332' WHERE CMT. WAS CIRC. TO SURFACE..

REMARKS: ALLIED CMT. 60/40 POZ. 4% GEL.  
I DID OBSERVE THIS PLUGGING.

  
Steve Van Gieson (AGENT)

FORM CP-2/3  
REV. 3/90

RECEIVED  
KANSAS CORPORATION COMMISSION

DEC 11 1995

CONSERVATION DIVISION  
WICHITA, KS

INVOICED

DATE 12-13-95

INV. NO. 44335

ow