

1090182

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,814-0000

C SE NE, SEC. 32, T 34 S, R 11 W/E

1980 feet from N/SX section line

760 feet from XX/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5255

Lease Name Rose Well # 1

Operator: McGinness Oil Company

County Barber

Name & Address 1026 Union Center Building

Well Total Depth 4807 156.23 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 386

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Dunne-Gardner Petroleum License Number 5426

Address 250 O. W. Garvey Building, Wichita, KS 67202

Company to plug at: Hour: 6:15 pm Day: 27 Month: May Year: 19 84

Plugging proposal received from John Tanner

(company name) Dunne-Gardner (phone) 316-265-1611

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 450' with 40 sx cement solid bridge

2nd plug hulls - plug at 40' -- cement to surface with 10 sx cement

4th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by R. B. Barburton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:15 pm Day: 27 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 450' with 40 sx cement, 2nd plug and 3rd plug - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 4th plug to circulate rat hole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JUN 11 1984

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

(If additional description is necessary, use BACK of this form.)

INVOICED (do not) observe this plugging.

Signed R. B. Barburton (TECHNICIAN)

DATE 6-12-84

INV. NO. 1958