

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-25725-00-01
Spot: SWNWSE Sec/Twnshp/Rge: 8-34S-10E
1470 feet from S Section Line, 2190 feet from E Section Line
Lease/Unit Name: BURKETT Well Number: 11
County: CHAUTAUQUA Total Vertical Depth: 1890 feet

Operator License No.: 30930
Op Name: PAR, INC.
Address: 1211 NORTH SHARTEL #405
OKLAHOMA CITY, OK 73103

Conductor Pipe: Size feet: 861.43
Surface Casing: Size feet: 40
Production: Size feet:
Liner: Size feet:

Well Type: EOR UIC Docket No: E25536.2 Date/Time to Plug: 11/08/2002 8:00 AM
Plug Co. Lcense No.: 5970 Plug Co. Name: ELMORE, JOHN A.
Proposal Rcvd. from: JOHN ELMORE Company: ELMORE, JOHN A. Phone: (316) 725-5744

Proposed Plugging Method: TO RUN 1" TUBING AND PUMP GEL AND CEMENT FOR BOTTOM, MIDDLE AND TOP PLUGS.

Plugging Proposal Received By: RON ROWE WitnessType: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 11/08/2002 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

RAN 1" HYDRIL TUBING TO 1750' INSIDE 4.5" CASING AND GELLED HOLE, THEN PUMPED 10 SACKS CEMENT FOR BOTTOM PLUG. PULLED 1" TO 1000' AND PUMPED 10 SACKS CEMENT FOR MIDDLE PLUG. PULLED 1" TO 500' AND PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 1" OUT AND TOPPED OFF WELL. USED TOTAL OF 2 SACKS GEL AND 70 SACKS CEMENT.

RECEIVED
KCC District #3
JAN 7 2003
RECEIVED
JAN 10 2003
KCC WICHITA
Charute CS

Remarks:

Plugged through:

District: 03

Signed

Ron Rowe by [Signature]
(TECHNICIAN)

INVOICE

DATE 1-10-03

INV. NO. 2003061065