

1 010152

117 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 8653

Operator: Petroleum Technologies, Inc.
Name & Address 3535 Broadway Suite C
Kansas City, MS 64111

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P. O. Box 189, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:00 am Day: 17 Month: July Year: 1986

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 5 1/2" at 5249' PBD 4350' Perfs at 4000-4004'

1st plug sanded back to 3950' and dumped 5 sx cement on top of sand through bailer

2nd plug squeezed well with 2 sx hulls, 10 sx gel, 30 sx cement, 10 sx gel, 1 sx hull,

released 8 5/8" plug and pumped 110 sx. cement.

Plugging Proposal Received by Jack L. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30 pm Day: 17 Month: July Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 3950' and dumped 5 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls and 150 sx. cement

RECEIVED
STATE CORPORATION COMMISSION
CONS. DIV. WICHITA, KS

Maximum pressure 100 psi and shut in 20 psi.

JUL 21 1986

Remarks: Recovered 3427' of 5 1/2" casing. Used Econolite by Halliburton.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

Signed Jack L. Luthi
(TECHNICIAN)

INVOICED

DATE JUL 23 1986

INV. NO. 14430 2-17