

To: **1040841** **4-25**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,498 -0000
NE NW SE, SEC. 1, T 34 S, R 13 W/E
2310 feet from S section line
1590 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6410
Operator: Petroleum Technical Services Co.
Name & Address 3000 N. Garfield St., Ste. 210
Midland, TX 79705

Lease Name Donovan "A" Well # 1
County Barber **163.99**
Well Total Depth 5046 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 512

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104-0187

Company to plug at: Hour: 1 p.m. Day: 25 Month: 4 Year: 19 94

Plugging proposal received from Jim Tucker

(company name) Petroleum Technical Services Co. (phone) 915-684-6603

Work: 4 1/2" at 5046' w/300 sx cement, Perfs at 5043-45'

1st plug sand back to 4990' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2 p.m. Day: 25 Month: 4 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4990' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls and 125 sx cement.

Maximum pressure 300 psi and shut in 200 psi.

No wiper plug-surface pipe plated with 4 1/2" collar.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3487' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
MAY 09 1994

observe this plugging.

DATE

INV. NO. 40402

Signed Stephen J. Gresham
(TECHNICIAN)

Handwritten notes:
100
Rec'd 94
5-2-94
JOG