

1070071

TO:

API NUMBER 15-007-22,489-~~62000~~

5-29

STATE CORPORATION COMMISSION

SW NW SW, SEC. 1, T 34 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION

1650 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

4950 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME DONOVAN "L" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY BARBER

OPERATOR LICENSE # 5123

WELL TOTAL DEPTH 3669.25' ^{119.25'} FEET

OPERATOR: PICKRELL DRILLING COM

PRODUCTION CSG: SIZE 4 1/2" FEET 3668.5'

NAME AND 110 N. Market, Suite 205

SURFACE CASING: SIZE 8 5/8" FEET 349'

ADDRESS Wichita, KANSAS 67202

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS 107 W. Fowler, P.O. Box 187, Medicine Lodge, Kansas 67104

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 29 MONTH: 5 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM ALAN VRATIL

(COMPANY NAME) CLARKE CORPORATION (PHONE) (316) 886-5665

WERE: PBTD 3668.5', Perfs at 3658-3659' CIBP @ 3550'

1st plug CIBP at 3550' w/2sx cement on top

2nd plug spot 10 sxs gel, 50 sxs cement at 650', 3rd plug at 370' with 50 sxs cement

4th plug 40-0' with 10 sxs cement

PLUGGING PROPOSAL RECEIVED BY Scott Alberg

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 11:50 DAY: 29 MONTH: 5 YEAR: 1998

ACTUAL PLUGGING REPORT 1st plug CIBP at 3550' w/2 sxs cement on top

2nd plug spot 10 sxs gel, 50 sxs cement at 650', 3rd plug at 370' with 50 sxs cement

4th plug 40-0' with 10 sxs cement. Good circulation throughout job.

RECEIVED
KANSAS CORPORATION COMMISSION


JUN 03 1998

CONSERVATION DIVISION
WICHITA, KS

REMARKS: Used Common Cement by Allied Cementing, Recovered 3000' of 4 1/2" casing.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED


(TECHNICIAN)

FORM CP-2/3



INVOICED

DATE 6-8-98

INV. NO. 50691

5-29