

7-615-007-10361-0000

To: 1 040437
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 10/15/56
SE SW NW, SEC. 1, T 34 S, R 13 W/E
2970 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6769
Operator: Westmore Drilling
Name & Address P.O. Box 347
Medicine Lodge, KS 67104

Lease Name Holmes Well # 2
County Barber 154.21
Well Total Depth 4745 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 305

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:15 p.m. Day: 6 Month: 7 Year: 19 90

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 7" at 4744' PBD 4730' Perfs at 4668-82'

1st plug sand above perfs to 4610' plus 5 sx cement on top with dump bailer,

2nd plug pump 400 lbs. hulls, 15 sx gel, 75 sx cement, 15 sx gel, 100 lbs. hulls, and

150 sx cement.

RECEIVED
JUL 11 1990
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Mike Spain
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 6 Month: 7 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4610' and dumped 5 sx cement on top of
sand bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 400 lbs. hulls, 15 sx gel, 75 sx cement,
15 sx gel, 100 lbs. hulls, and 150 sx cement.

Maximum pressure 250 psi and shut in 200 psi.

Note: No wiper plug. Pumped through 2" collar welded in surface pipe.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3200' of 7" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (and this mark) observe this plugging.

DATE 7-18-90

INV. NO. 28626

Signed Stephen J. Pfeifer
(TECHNICIAN)