

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 10 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Maxey of Pioneer Prod. has this

date requested permission to plug the following described well:

Mr. Maxey guarantees payment of the plugging fee.

Operator's full Name: Pioneer Production Corporation

Complete Address: Box 2542, Amarillo, Texas

Lease Name: Adams Well No. 1

Location: NE/4 Sec. 21 Twp. 34 Rge. 29 (E) (W)

County: Meade Total Depth 3375' Oil Well         

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Maxey was instructed to plug the well as follows:

7" to 1370' circulated w/ cement. 2 7/8" to 3370' cemented.

Top perforations 3278' Plug bottom w/ 20 sacks cement

Top of cement 3270' Pump 200 sacks cement in disposal formation

Mud to 800' Spot 35 sacks cement 800' to 650'

Mud 650' to 40' Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent