

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 5 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of Texaco Inc. has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name: Adams o/a Well No. 1

Location: C NE NE Sec. 19 Twp. 34 Rge. 29 XX (E) (W)

County Meade Total Depth 5900' Oil Well X

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1666' circulated w/ cement. 5 1/2" to 6050' cemented.

Top perforations 5892' Plug bottom w/ 20 sacks cement.

Top of cement 5800' Mud 5800' to 900'

Spot 35 sackscement 900' to 800' Mud 800' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Fries
Conservation Division Agent