



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAY 28 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Lauck of Thomas & Brewer has this

date requested permission to plug the following described well:

Mr. Lauck guarantees payment of the plugging fee.

Operator's full Name: Thomas & Brewer

Complete Address: Drawer 1248 Liberal, Kansas

Lease Name: Adams Well No. 1-16

Location: NE SW Sec. 16 Twp. 34 Rge. 29 (E) (W)

County Meade Total Depth 5890' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Lauck was instructed to plug the well as follows:

8 5/8" 1375' Cir.w/cem. 4 1/2" 5890' Cem. Top perf. 5808'

Plug bottom w/43 sax.cement. 5890' to 5566' Mud 5566' to 710'

Rock bridge 710' to 700' 35 Sax.cement 700' to 600'

Mud 600' to 50' Rock bridge 50' to 40' 13 Sax.cement 40' to 0'

Very truly yours,

Hugh Scott
 Conservation Division Agent