

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

STATE CORPORATION COMMISSION

SEP 14 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Shenandoah Oil has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Shenandoah Oil Corporation

Complete Address: 1500 Commerce Bldg., Fort Worth, Texas

Lease Name: H.G. Adams Well No. 1

Location: C SE SE Sec. 16 Twp. 34 Rge. 29 (E)(W)

County: Meade Total Depth 3320 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 612' circulated w/ cement 2 7/8" to 3319' cemented.

Top perforations 3258' Plug bottom w/ 10 sacks cement

Top of cement 3100' Mud 3100' to 600'

Spot 35 sacks cement 600' to 500' Mud 500' to 40'

Plug, HULLS & 10 sacks cement 40' to 0'.

Very truly yours,


Conservation Division Agent