



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Trigg has this
date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Trigg Exploration Company

Complete Address: 410 Woolworth Bldg., Boulder, Colo

Lease Name: Adams Well No. 1-12

Location: C NW Sec. 12 Twp. 34 Rge. 28 XX (E) (W)

County: Meade Total Depth 3144' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 538' circulated w/ cement. 5 1/2" to 3144' cemented


Top perforations 2993' Plug bottom w/ 20 sacks cement.

Top of cement 2850' Mud 2850' to 538'

Spotted 35 sacks cement 538' to 438' Mud 438' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent