

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 2 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ninney of Cities Service Oil Co. has this date requested permission to plug the following described well:

Mr. Ninney guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 6, Liberal, Kansas

Lease Name: Stalcup "F" Well No. 1

Location: C SE SW Sec. 30 Twp. 34 Rge. 35 (E)(W)

County Stevens Total Depth 6800' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Ninney was instructed to plug the well as follows:

8 5/8" to 1702' circulated w/ cement. T.D. 6800'

Mud 6800' to 6350' Spotted 35 sacks cement 6350' to 6250'

Mud 6250' to 2800' Spotted 70 sacks cement 2800' to 2600'

Mud 2600' to 700' Spotted 35 sacks cement 700' to 600'

Mud 600' to 45' Plug, Halls & 15 sacks cement 45' to 0'

Very truly yours,

Edgar J. Eves
Conservation Division Agent