

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 19 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Casey of Cities Service Oil has this date requested permission to plug the following described well:

Mr. Casey guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 1228, Guymon, Oklahoma

Lease Name: Minor "B" Well No. 1

Location: C SW NE Sec. 13 Twp. 33 Rge. 42 XX (E) (W)

County: Morton Total Depth 5762' Oil Well

Gas Well X Input Well  SWD Well  D & A X Lost Hole

Mr. Casey was instructed to plug the well as follows:

8 5/8" to 1481' circulated w/ cement. 4 1/2" to 5155' cemented.

Top perforations 4989' Plug bottom w/ 50 sacks cement

Top of cement 4500' Mud 4500' to 750'

Spot 50 sacks cement 750' to 600' Mud 600' to 30'

Plug, Halls & 10 sacks cement 30' to 0'.

Weld Plate on 8 5/8" casing.

Very truly yours,

Conservation Division Agent