

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 14 1982  
6-14-82  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Jim Barlow of Gabbett & Jones (Reg 12) has this date requested permission to plug the following described well:

Operator's Full Name: Canadarko Production Company

Complete Address: P.O. Box 351 Liberal, Kans. 67901

Lease Name: Hepp Well No. 'A' - #1

Location: 1820' FWL. - 785' F.S.L. SW Sec. 21 Twp. 33 Rge. 38 (E) (W)

County: Stevens Total Depth: 6625 FT.

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Barlow was instructed to plug the well as follows:

8 5/8" - 1695 FT SP. CUC. w/ 950<sup>ST</sup> Common - 3% CC + Formid 4% CC.

Ordered 155<sup>ST</sup> Common Cnt. w/ 2% Ca-Cl. + 8 5/8" Plug.

Spot with Drill Stem - with heavy mud between all plugs.

1<sup>ST</sup> Plug @ 2450 FT w/ 40<sup>ST</sup> Cnt.

2<sup>ND</sup> Plug @ 1750 FT w/ 40<sup>ST</sup> Cnt.

3<sup>RD</sup> Plug @ 810 FT w/ 35<sup>ST</sup> Cnt.

4<sup>TH</sup> Plug <sup>solid Budge</sup> @ 60 FT w/ 20<sup>ST</sup> Cnt.

10<sup>ST</sup> In Rat Hole

10<sup>ST</sup> In mouse hole

Marion Schmidt  
Conservation Division Agent  
Verbal orders By Don Thompson