

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 20 1962

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Paul Gattin of Anadarko Production Co. has this
 date requested permission to plug the following described well:

Mr. Paul Gattin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351 Liberal, Kansas

Lease Name: Hayward Well No. # A-2

Location: App. C SW/4 50' N & 50' W of C-SW/4 Sec. 36 Twp. 34 S Rge. 40 (E) (W)

County Morton Total Depth 6818' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Paul Gattin was instructed to plug the well as follows:

8 5/8" 1699' Circulated w/900 sax.cement.

Mud 6818' to 2850' 150 sax.cement 2850' to 2400'

Mud 2400' to 700' Plug and 45 sax.cement 700' to 565'

Mud 565' to 50' Plug and 15 sax.cement 50' to 5'

Very truly yours,

[Signature]
 Conservation Division Agent