

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

23 January 1982

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-129-20592

RECEIVED
STATE CORPORATION COMMISSION
FEB - 2 1982
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Jim Barlow of Anadarko Products has this

date requested permission to plug the following described well:

Operator's Full Name: Anadarko Production Co.

Complete Address: Box 351 Liberal Kansas 67901

Lease Name: Buddens Well No. A1

Location: NW NW Sec. 27 Twp. 34 Rge. 4016 (E) (W)

County: Morton Total Depth: 662-1

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Barlow was instructed to plug the well as follows:

There is 1710' of surface pipe cement circulated, 1st plug
push rubber plug to 1650' and pumped 40 sks of cement
on top of it, 2nd plug spot 135' sks of cement at 800'
3rd plug 40' to 0' with 10 sks of cement on solid bridge. This
also pumped 10 sks of cement in rat hole & 5 sks of cement in
mouse hole. Plugging accomplished by Halliburton Co.

Very truly yours,

Paul Little
Conservation Division Agent