

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 5 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Patrick has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: R.J. Patrick

Complete Address: 1800 N. Cain, Liberal, Kansas

Lease Name: Mingenback Well No. 1-22

Location: C SE NW Sec. 22 Twp. 34 Rge. 40 (E) (W)

County: Morton Total Depth 6396' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

7 5/8" to 2664' circulated w/ cement. 4 1/2" to 61148' cemented.


Top perforations 6372' Plug bottom w/ 20 sacks cement.

Top of cement 6000' Mud 6000' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent