

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
SEP 10 1966  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. McCune of Cities Service Oil Co. has this  
date requested permission to plug the following described well:

Mr. McCune guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 1028, Guymon, Oklahoma

Lease Name: Mingenback "B" Well No. 1

Location: C SE NW Sec. 18 Twp. 34 Rge. 40 (E) (W) XX

County Morton Total Depth 6510' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. McCune was instructed to plug the well as follows:

8 5/8" to 1651' circulated w/ cement. 4 1/2" to 5570' cemented.

Top perforations 5491' All Perforations squeezed off.

Top of cement 5420' Mud 5420' to 2440'

Spotted 50 sacks cement 2440' to 2285' Mud 2285' to 704'

Spotted 35 sacks cement 704' to 604' Mud 604' to 34'

Plug, Hulls & 10 sacks cement 34' to 0'.

Very truly yours,

Edgar J. Evers  
Conservation Division Agent