

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Nabob has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.Operator's full Name: Nabob Production CompanyComplete Address: Box 448, Amarillo, TexasLease Name: H.G. Adams Well No. 1Location: NE SE Sec. 7 Twp. 34 Rge. 29 (E) (W)County: Meade Total Depth 6475' Oil WellGas Well X Input Well SWD Well D & A X Lost HoleMr. Sargent was instructed to plug the well as follows:8 5/8" to 1516' circulated w/ cement. 4 1/2" to 6462' cemented.Top perforations 5976' Plug bottom w/ 15 sacks cementTop of cement 5500' Mud 5500' to 900'Spotted 35 sacks cement 900' to 800' Mud 800' to 45'Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Evans
Conservation Division Agent