

15-077-10149-0000

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission  
 CONSERVATION DIVISION  
 (Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 26 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Doug Payne of Kent Well Service has this date requested permission to plug the following described well:

Mr. V. W. McKneb guarantees payment of the plugging fee.

Operator's full Name: V. W. McKneb

Complete Address: Box 808, Winfield, Kansas

Lease Name: Welch Well No. #1

Location: XXXXXX NW - NW Sec. 12 Twp. 34 Rge. 6 (E)(W) W

County Harper Total Depth 3822' Oil Well X (Abandoned)

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Doug Payne was instructed to plug the well as follows:

3821' of 4 1/2" long string perforated at 3790' to 3797'. Pipe sanded to 3780' with three sacks of cement. 300' of 8 5/8" surface pipe circulated with 300 sacks of cement. Hole filled to 200' with mud, 10' rock bridge, 20 sacks of cement. Hole filled to 40' with mud, 10' rock bridge, 10 sacks of cement to base of cellar.

Very truly yours,

*Herman Justus*  
 Conservation Division Agent