

State of Kansas



WM. H. AVERY	Governor
WILLIAM L. MITCHELL	Chairman
JAMES O. GREENLEAF	Commissioner
HARRY G. WILES	Commissioner
RAYMOND B. HARVEY	Secretary
E. EDWARD JOHNSON	Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
CONSERVATION COMMISSION
APR 6 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill
filed March 22, 1967.

Dear Sir:

Mr. Otto Bernes of Donelson Drilling Company has this date requested permission to plug the following described well:

Mr. Bernes guarantees payment of the plugging fee.

Operator's full Name: J. A. Allison

Complete Address: 1415 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Mattingley Well No. # 1

Location: C NE NW Sec. 12 Twp. 34 Rge. 6 (E)(W) W

County Harper Total Depth 3800' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bernes was instructed to plug the well as follows:

241' of 8 5/8" surface pipe, cement circulated with 175 sacks. Fill hole with drilling mud to 225', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 20 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Aubie Elving
Conservation Division Agent