

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217RECEIVED  
STATE CORPORATION COMMISSIONVERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

SEP 08 1975

CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Reddick of Da Mac Drlg Inc has this  
date requested permission to plug the following described well:Mr. Reddick guarantees payment of the plugging fee.Operator's full Name: Godsey-Earleughen IncComplete Address: 7030 S. Yale Tulsa, OKLease Name: Wilcox Well No. 1Location: SW/SW/SW Sec. 15 Twp. 34s Rge. 6 (E)(W) WCounty: Harper Total Depth 4610 Oil Well Gas Well  Input Well  SWD Well  D & A X Lost Hole Mr. Reddick was instructed to plug the well as follows:307 ft 8 5/8 surface cemented with 250 sacks. Pump plug.35 sacks cement to 240 ft. Mud to 40 ft, plug, 1/2 sackhulls, 15 sacks cement to surface. 2 sacks cement in rathole, 2 in mouse hole.Pumped by Halliburton Cementing Great Bend, KS

Very truly yours,