

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION  
DEC 23 1970  
CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Anadarko has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.Operator's full Name: Anadarko Production CompanyComplete Address: Box 351, Liberal, Kansas 67901Lease Name: Low "A" Well No. 4Location: C W/2 SE Sec. 8 Twp. 33 Rge. 40 (E) (W)County: Morton Total Depth 5824' Oil Well XGas Well Input Well SWD Well D & A X Lost HoleMr. Sargent was instructed to plug the well as follows:8 5/8" to 1510' circulated w/ cement. 5 1/2" to 5823' cemented.Top perforations 5576' Plug bottom w/ 25 sacks cement.Top of cement 4960' Mud 4960' to 900'Spot 35 sacks cement 900' to 800' Mud 800' to 45'Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent