

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Anadarko Prod. has this
date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Comapny

Complete Address: Box 351, Liberal, Kansas

Lease Name: Low "A" Well No. 5

Location: G NE SW Sec. 8 Twp. 33 Rge. 40 ~~(E)~~ (W)

County: Morton Total Depth 5684' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1527' circulated w/ cement. 4 1/2" to 5683' cemented.

Top perforations 5626' Plug bottom w/20 sacks cement

Top of cement 5400' Mud 5400' to 950'

Spot 35 sacks cement 950' to 850' Mud 850' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent