

State of Kansas



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 15 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Barker of Anadarko Production Co. has this date requested permission to plug the following described well:

Mr. Barker guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351 Liberal, Kansas

Lease Name: Low Well No. A-7

Location: C SW SW Sec. 8 Twp. 33S Rge. 40 (E) (W)

County Morton Total Depth 5660' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Barker was instructed to plug the well as follows:

8 5/8"-1527' Circulated w/cement.

Mud 5660' to 2750' Spotted 50 Sax.cement 2750' to 2602'

Mud 2602' to 686' Spotted 35 Sax.cement 686' to 586'

Mud 586' to 45' Plug,Hulls,15 sax.cement 45' to 0

Very truly yours,

Conservation Division Agent