

15-175-00 395-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1966

RECEIVED
STATE CORPORATION COMMISSION

APR 25 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION

Operator's Full Name Mallomee-Coppinger Operations Incorporated

Complete Address: 1207 Union National Building, Wichita, Kansas

Lease Name Keating Well No. 1

Location SW SW Sec. 33 Twp. 34 Rge. 34 (E) (W)

County Seward Total Depth 6650'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 7:00PM Day 21 Month 4 Year 1966

The Above well was plugged as follows:

8 5/8" to 1366' circulated w/ cement. T.D. 6650' - 4 1/2" to 4488

Top Perforations 4380' Plug bottom w/ 20 sacks cement.

Top of cement 4200' Mud 4200' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 45'

Plug, Hulls & 15 sacks cement 45' to 0.

Pulled 3516' of 4 1/2" Casing. Company Pump.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Eves
Well Plugging Supervisor

DATE 4/26/66
INV. NO. 3100-W