

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 13 1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-625-2051-0000 (of this well)

Operator's Full Name Northern Natural Gas Company

Complete Address Box 872, Woodward, Oklahoma 73801

Lease Name Gabbert Trust Well No. 1-34

Location 1250' FSL & 1250' FEL SE/4 Sec. 34 Twp. 34 Rge. (E) (W) 24

County Clark Total Depth 6043'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Lillard Casing Pulling

Address Woodward, Oklahoma License No. 618

Operation Completed: Hour 5 P Day 3 Month 2 Year 1978

The above well was plugged as follows:

Total Depth 6043' 8 5/8 csg set 705' cwc

4 1/2 csg set 6035' cw 125 sk cem. P FS (5621'-5625')

Pumped 2 hulls & 10 sk cmt down 4 1/2 csg. Top of cem. 5500'

Filled hole with gel & water - Cutoff & recovered 4995' Of 4 1/2 csg.

Set 50 sk cem plug (755'-655') thru 4 1/2 csg.

Set 10 sk cmt plug (33'-3')

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 2-14-78

INV. NO. 6755-W