

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-129-21281-0001 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. 8/97

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE (316) 624-6253

LEASE USA AQ WELL# 1H SEC. 27 T. 34S R. 40 (xxxx/West)

SE - SE - NW - NW SPOT LOCATION/QQQQ COUNTY MORTON

1250 FEET (in exact footage) FROM x/N (circle one) LINE OF SECTION (NOT Lease Line)

1250 FEET (in exact footage) FROM x/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL ☐ GAS WELL ☒ D&A ☐ SWD/ENHR WELL ☐ DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8" SET AT 753' CEMENTED WITH 490 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 3185' CEMENTED WITH 330 SACKS

PERFS: 3141-46, 3109-15, 3071-74, 2964-68,
LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: 2883-2913, 2602-08, 2538-45, CIBPS: 3100', 3050'
2950', 2850'

ELEVATION 3389' / -- T.D. 3190' PBDT 2850' ANHYDRITE DEPTH
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD ☒ POOR ☐ CASING LEAK ☐ JUNK IN HOLE ☐

PROPOSED METHOD OF PLUGGING NOTIFY KCC DISTRICT OFFICE 72 HRS PRIOR TO PLUGGING. MIRU CSG PULLERS. SET CIBP @ 2500'. SPOT 2 SKS CLASS H CMT ON TOP OF CIBP. DISPLACE W/59 BBLs 9PPG MUD. PULL FREE PT ON 5-1/2" CSG & SHOOT OFF. SPOT 35 SKS CLASS H CMT @ CUT-OFF DEPTH. PULL CSG TO 803'. SPOT 35 SKS CLASS H CMT FROM 803'-703'. PULL CSG TO 53'. SPOT 17 SKS CLASS H CMT FROM 53'-3'. TOH W/5-1/2" CSG. CUT OFF & CAP 8-5/8" CSG 3' BELOW GL & PERMANENTLY INSCRIBE CAP. RDMO CSG PULLERS. RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? (LOGS SUBMITTED WITH ACO-1)

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

MR. TERRY LEWIS PHONE# (316) 697-2188

ADDRESS P.O. DRAWER X City/State ELKHART, KANSAS 67950

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1/31/97 AUTHORIZED OPERATOR/AGENT: John A. Broman

JOHN A. BROMAN (signature)
DIVISION PRODUCTION ENGINEER



Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

February 4, 1997

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

USA AQ #1H
API 15-129-21,281
1250 FNL 1250 FWL
Sec. 27-34S-40W
Morton County

Dear Mr. Terry Lewis,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760