

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-189-21541-000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549  
(owner/company name) (operator's)  
ADDRESS P.O. BOX 351 CITY LIBERAL  
STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE (316) 624-6253  
LEASE LIGHT "U" WELL# 1 SEC. 29 T. 33S R. 38 (xxxx/West)  
- - SE - SE SPOT LOCATION/QQQQ COUNTY STEVENS

990 FEET (in exact footage) FROM S/X (circle one) LINE OF SECTION (NOT Lease Line)  
1320 FEET (in exact footage) FROM E/X (circle one) LINE OF SECTION (NOT Lease Line)

**Check One:** OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_  
CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS  
SURFACE CASING SIZE 8-5/8" SET AT 1715 CEMENTED WITH 760 SACKS  
PRODUCTION CASING SIZE 5-1/2" SET AT 6317 CEMENTED WITH 225 SACKS  
CIBP @ 6198, CMT RETAINER @ 6220  
LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: 6180-6181, 6200-6201, 6173-6190, 6223-6225  
ELEVATION 3196 / \_\_\_\_\_ T.D. 6650 PBDT 6198 ANHYDRITE DEPTH NA  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING MIRU. SPOT 2 SXS HULLS & 20 SXS CMT FROM 6173-6014'. PULL FREE POINT AND CUT OFF 5-1/2" CSG. SPOT 40 SXS CMT @ CUT OFF DEPTH. PULL UP HOLE & SPOT 40 SXS @ 1765-1665, PULL UP HOLE & SPOT 40 SXS @ 650 -550'. PULL UP HOLE & SPOT 20 SXS @ 53-3'. CUT OFF 8-5/8" CSG 3' BELOW GL AND CAP. INSCRIBE CAP, RDMO, RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG.

**PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.**

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

MR. Curtis Clark PHONE# (316) 544-4344

ADDRESS P.O. BOX 40 City/State HUGOTON, KANSAS 67951

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151  
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

**PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT**

DATE: 7/27/98 AUTHORIZED OPERATOR/AGENT: Shawn D. Young

SHAWN D. YOUNG (Signature)  
DIVISION PRODUCTION ENGINEER

RECEIVED  
KANSAS CORP COMM  
JUL 29 12:02  
1998



## Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Susan M. Seltsam, Commissioner Cynthia L. Claus, Commissioner

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

July 29, 1998

Anadarko Petroleum Corporation  
PO Box 351  
Liberal, Ks. 67905-0351

Light "U" #1  
API 15-18921541  
SE SE  
Sec. 29-33S-38W  
Stevens County

Dear Curtis Clark,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City, KS 67801  
(316) 225-8888