

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-175-21010-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Shepler & Thomas, Inc. OPERATORS LICENSE NO. 3711

ADDRESS P.O. Box 1162 Liberal, KS 67905-1162 PHONE # (316) 624-0750

LEASE (FARM) Johnson WELL NO. 1-19 WELL LOCATION SE-SW COUNTY Seward

SEC. 9 TWP. 34S RGE. 32 (E) or (W) TOTAL DEPTH 6500' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 1581 CEMENTED WITH 600 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT N/A

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Mud from 6500 to 1690, 50 sx

50/50 poz from 1690 to 1590, mud from 1590 to 780, 30 sx same cement from

780 to 680, mud to 40 ft. 10 sx same cement to 3' below ground level. 15 sx

(If additional space is needed use back of form)

same cement in rathole, 10 sx in mousehole.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 1:00 P.M. on 3-17-88

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

R. F. Burke PHONE # (316) 624-0750

ADDRESS P.O. Box 1162 Liberal, Kansas 67905-1162

PLUGGING CONTRACTOR Halliburton Services LICENSE NO. _____

ADDRESS West Highway 54 Liberal, Kansas 67901 PHONE # (316) 624-3879

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: R. F. Burke
(Operator or Agent)

DATE: 3-24-88

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date: March 4, 1988

API Number 15-175-21,010-0000

OPERATOR: License # 737-6684-3711
Name Shepler & Thomas, Inc.
Address P.O. Box 1162
City/State/Zip Liberal, Kansas 67905-1162
Contact Person R. F. Burke
Phone (316) 624-0750

N 1/2 SE SW, Sec. 9, Twp. 34 S, Rg. 32
960 660 3300
Ft. from South Line of Section
Ft. from East Line of Section

CONTRACTOR: License # 5147
Name Unknown
City/State

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 660 feet
County Seward
Lease Name Johnson Well # 1-19

Well Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
X Gas Inj X Pool Ext. Air Rotary
OWWO Expl Wildcat Cable

Ground surface elevation 2760 feet MSI
Domestic well within 330 feet: yes X no X

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Municipal well within one mile: yes X no
Depth to bottom of fresh water 300 680
Depth to bottom of usable water 1100 680
Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 1600
Conductor pipe required 40
Projected Total Depth 6500 feet
Formation St. Louis

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 2/26/88 Signature of Operator or Agent [Signature] Title Agent

For KCC Use:
Conductor Pipe Required 9-3-88 feet; Minimum Surface Pipe Required 700 feet per Alt.
This Authorization Expires 9-3-88 Approved By [Signature] 3-3-88

EFFECTIVE DATE: 3-8-88
SPUD 3-4-88
Gungwas
E-54 Hair - NW

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep 5600 or formation with 100 feet of 60/40 poz. 6% gel
2nd plug @ ft. deep 1700 or formation with 200 feet of same
3rd plug @ ft. deep 40 or formation with 40 feet of same
4th plug @ ft. deep or formation with feet of
5th plug @ ft. deep or formation with feet of
(2) Rathole to surface minus 5 feet 5 SX (b) Mousehole to surface minus 5 feet 5 SX

PUSHER Gary Marshall
TD 6500 FORMATION MISS ST. LOUIS 5730-
SURFACE PIPE 8 1/2 @ 15 8/16 4779
ANHYDRITE 1700 ELEVATION 1776
STARTING TIME & DATE 1:33 0-8-19-88
COMPLETION TIME & DATE 5:00 3-19-88 SX
1st PLUG @ 1590 FT. W/ 50 SX
2nd PLUG @ 780 FT. W/ 30 SX
3rd PLUG @ 40-0 FT. W/ 10 SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ W.W. SX
CEMENT COMPANY Halliburton
6 Am. 5 8/16
TECHNICIAN

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1988

CONSERVATION DIVISION
Wichita, Kansas