

7

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-175-217650000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

8/99

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE ALEXANDER "C" WELL# 2 SEC. 4 T. 34S R. 32 (XXXX/West)
70' N & 70' W OF

- - C - NW SPOT LOCATION/QQQQ COUNTY SEWARD

1250 FEET (in exact footage) FROM N/X (circle one) LINE OF SECTION (NOT LeaseLine)

1250 FEET (in exact footage) FROM X/W (circle one) LINE OF SECTION (NOT LeaseLine)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 523' CEMENTED WITH 210 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 3310' CEMENTED WITH 320 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3132-3140, 3160-3170, 3180-3187, 3198-3208, 3216-3224, 3240-3250, CIBP @ 3000', 2652-2662, 2616-2624.

ELEVATION 2768.6- T.D. 3320 PBDT 3000 ANHYDRITE DEPTH 1600
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____
PROPOSED METHOD OF PLUGGING MIRU PU. TIH W/BAILER & SPOT 2 SXS ON TOP OF CIBP @ 3000'. TOH. MIX & PUMP 3 SKS HULLS & 50 SKS 60/40 POZ W/6% GEL TO PLUG PERFS @ 2616-2662'. DISPLACE W/9PPG MUD. LOCATE FREE POINT AND SHOOT OFF 5-1/2" CSG. TOH W/CSG TO 573' & SPOT 50 SKS CMT FROM 473' TO 573'. TOH W/CSG TO 54' & SPOT 15 SKS FROM 54' TO 4'. TOH W/REMAINING CSG. CUT OFF & CAP 8-5/8" CSG 4' BELOW GL. INSCRIBE WELL NAME & NUMBER, LEGAL DESCRIPTION AND DATE PLUGGED ON STEEL CAP. RD PLUGGERS & RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? FILED WITH ORIGINAL ACO-1

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

JIM BARLOW PHONE# (316) 624-6253

ADDRESS P. O. BOX 351 City/State LIBERAL, KANSAS 67905-0351

PLUGGING CONTRACTOR: HALLIBURTON ENERGY SERVICES KCC LICENSE # 5287
(company name) (contractor's)

ADDRESS P. O. BOX 1598 LIBERAL, KS 67905-1598 PHONE # (316) 624-3879

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1/19/99 AUTHORIZED OPERATOR/AGENT: David W. Kapple
DAVID W. KAPPLE (signature)
DIVISION DRILLING ENGINEER



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner
NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 21, 1999

Anadarko Petroleum Corporation
PO Box 351
Liberal, Ks. 67905-0351

Alexander "C" #2
API 15-17521765
70N 70W C NW
Sec. 4-34S-32W
Seward County

Dear Jim Barlow,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,
Handwritten signature of David P. Williams in cursive.

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-8888