

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 1517520476-0001 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS 701 S. TAYLOR, STE 400 CITY AMARILLO

STATE TEXAS ZIP CODE 79101 CONTACT PHONE (806) 457-4600

LEASE DODD WELL# B-2 SEC. 18 T. 34S R. 32 (xxxx/West)

- C - NW - SW SPOT LOCATION/QQQQ COUNTY SEWARD

1980 FEET (in exact footage) FROM S/X (circle one) LINE OF SECTION (NOT Lease Line)

660 FEET (in exact footage) FROM X/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8 SET AT 1572 CEMENTED WITH 800 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 6404 CEMENTED WITH 400 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: PREs: 6315-6324, 6253-6271, 5178-5192, 5004-5008; CIBP: 6300; CMT RTR: 6216

ELEVATION 2804 / XXXX T.D. 6405 PBDT 6216 ANHYDRITE DEPTH
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING RIH AND SET CIBP AT 4950. DUMP 2 SXS CMT ON PLUG. SHOOT OFF 5 1/2 CSG AT FREE POINT. LOAD HOLE WITH 9 PPG MUD AND TOH TO 1670. SPOT 50 SXS CMT FROM 1670 TO 1520. TOH TO 700. SPOT 50 SXS CMT FROM 700 TO 550. TOH TO 40. SPOT 15 SXS CMT FROM 40 TO 4. TOH WITH REMAINING 5 1/2 CSG. CUT OFF AND CAP 8 5/8 CSG 4 BELOW GL.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

DAVID RELEFORD PHONE# (620) 482-1000

ADDRESS 1707 W 2ND City/State LIBERAL, KS 67901

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3/18/2003 AUTHORIZED OPERATOR/AGENT: Craig R. Walters

CRAIG R. WALTERS, P.E. (Signature)
DIVISION PRODUCTION ENGINEER

RECEIVED

MAR 21 2003

KCC WICHITA



15-175-20476-0001

Kansas Corporation Commission

Kathleen Sebelius, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Anadarko Petroleum Corporation
1201 Lake Robbins Drive
The Woodlands, TX 77380

March 24, 2003

Re: DODD B #2
API 15-175-20476-00-01
CNWSW 18-34S-32W, 1980 FSL 660 FWL
SEWARD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888

Sincerely

David P. Williams
Production Supervisor