

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 17 1970

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Burris of Leben et al has this  
date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Leben et al

Complete Address: 200 W. Douglas, Wichita, Kansas

Lease Name: Siemens Well No. 1

Location: SW SW SW Sec. 10 Twp. 34 Rge. 32 (E) (W)

County: Seward Total Depth 6498' Oil Well

Gas Well X Input Well      SWD Well      D & A X Lost Hole     

Mr. Burris was instructed to plug the well as follows:

8 5/8" to 1505' circulated w/ cement. Mud 6498' to 1100'  
Spot 35 sacks cement 1100' to 1000' Mud 1000' to 45'  
Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent