



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

1 May 1982

RECEIVED
STATE CORPORATION COMMISSION

MAY - 6 1982

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-175-20,617-0000

Dear Sir:

Mr. *Mark Pinick* of *Arey Corporation* has this date requested permission to plug the following described well:

Operator's Full Name: *Arey Corporation*

Complete Address: *1670 Broadway Suite 3301, Denver Colo. 80202*

Lease Name: *Mikols* Well No. *1*

Location: *C-SE-SE-SW* Sec. *20* Twp. *34* Rge. *32* (E) (W)

County: *Seward* Total Depth: *6580'*

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated:

Mr. *Pinick* was instructed to plug the well as follows:

They cement circulated 1580' of 8 1/8" surface casing. 1st plug at 1580' with 60 sby of cement. 2nd plug at 780' with 35 sby of cement 3rd plug 40' to 0' on solid bridge with 10 sby of cement. Then circulate 10 sby of cement in ^{rat} mouse hole & 5 sby of cement in mouse hole. The water well was plugged with 3 sby of cement. They pumped down ^(over)

Very truly yours,

Paul A. Luthin
Conservation Division Agent

Cement with 2% C.C. through drill pipe with hole full
of heavy mud. The plugging was accomplished
by Western Cementing.