

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 25 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Tracy of Horizon Oil & Gas has this

date requested permission to plug the following described well:

Mr. Tracy guarantees payment of the plugging fee.

Operator's full Name: Horizon Oil & Gas Company

Complete Address: Box 7, Spearman, Texas

Lease Name: Adams "A" Well No. 1-36

Location: C NE NW Sec. 36 Twp. 34 Rge. 31 (E)(W)

County Seward Total Depth 6253 Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Tracy was instructed to plug the well as follows:

8 5/8" to 1400' circulated w/ cement. 4 1/2" to 6244' cemented.

Top perforations 6103' Plug bottom w/ 10 sacks cement.

Top of cement 6000' Mud 6000' to 690'

Spotted 40 sacks cement 690' to 570' Mud 570' to 35'

Plug, Hulls & 5 sacks cement 35' to 0' Company Pump

Very truly yours,

Edgar J. Eves
Conservation Division Agent