

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lofland of Ted R. Lofland has this

date requested permission to plug the following described well:

Mr. Lofland guarantees payment of the plugging fee.

Operator's full Name: Ted R. Lofland

Complete Address: Box 85, Liberal, Kansas 67901

Lease Name: Jenettie Long Well No. 1

Location: C NW NW Sec. 33 Twp. 34 Rge. 31 XX (E) (W)

County: Seward Total Depth 6800' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Lofland was instructed to plug the well as follows:

13 3/8" to 675' circulated w/ cement. 9 5/8" to 2646' cemented.

5 1/2" to 6050' cement. Top perforations 5959' to 85'

Plug bottom w/ 20 sacks cement. Top of cement approx 5000'

Mud 5000' to 417' Spot 60 sacks cement 417' to 300'

Mud 300' to 45' Bridge & 25 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent