

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 19 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Nenney of Cities Service Oil has this date requested permission to plug the following described well:

Mr. Nenney guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 1098, Liberal, Kansas

Lease Name: Fitzgerald "A" Well No. 2

Location: C NW SE Sec. 8 Twp. 34 Rge. 33 (E)(W)

County: Seward Total Depth 4560' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Nenney was instructed to plug the well as follows:

8 5/8" to 771' circulated w/cement. Mud 4560' to 4350'

Spot 30 sacks cement 4350' to 4250' Mud 4250' to 2900'

Spot 125 sacks cement 2900' to 2475' Mud 2475' to 750'

Spot 35 sacks cement 750' to 600' Mud 600' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Edgar J. Evers
Conservation Division Agent