

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Sutton of Panhandle Eastern has this  
date requested permission to plug the following described well:

Mr. Sutton guarantees payment of the plugging fee.

Operator's full Name: Panhandle Eastern Pipelina Co.

Complete Address: Box 828, Liberal, Kansas

Lease Name: Wood Well No. 1

Location: C NE SW Sec. 36 Twp. 34 Rge. 32 (W)

County Seward Total Depth 6605' Oil Well

Gas Well X Input Well      SWD Well      D & A X Lost Hole     

Mr. Sutton was instructed to plug the well as follows:

13 3/8" to 652' circulated w/ cement. 9 5/8" to 2599' cemented.

5 1/2" to 6149' cemented. Top perforations 5103'

Plug bottom w/ 50 sacks cement. Top of cement 4900'

Mud 4900' to 191' Rock Bridge & 50 sacks cement 191' to 120'

Mud 120' to 30' Plug, Halls & 25 sacks cement 30' to 0'

RECEIVED  
STATE CORPORATION COMMISSION

SEP 11 1967

CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

Edgar J. Eves  
Conservation Division Agent