

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION NE-NW-SW, Sec. 14, T 34 S, R 21 W  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- -025-2037-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 7744

Lease Name Hayden Well # 1-14

Operator: Sho-Bar Energy Inc.  
Name & Address Box 217, Hayden Kans  
67058

County Clay \$ 193.13

Well Total Depth 5518 feet  
Production 1 1/2 @ 5454'  
Conductor Pipe: Size 8 3/4 feet 850  
Surface Casing: Size 8 5/8 feet 850

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated This well was tested but never produced

Plugging Contractor Sargants Casing Pulling License Number 6547

Address 620 S. Lincoln, Box 506 Liberal Kans 67901

Company to plug at: Hour: 10:00 AM Day: 22 Month: 9 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Dan Houlton

(company name) Sargants Casing pulling Inc. (phone) \_\_\_\_\_

were: 1st plug pumped 2 sky bulbs + 20 sky cement on bottom  
2nd plug @ 900' w/ 40 sky cement 3rd plug @ 360' w/ 30  
sky cement, 4th plug @ 40' to 0' w/ 10 sky cement on solid  
ledge. The plugging accomplished by Sargants  
Casing pulling w/ common socket cement. The cement  
was pumped through 4" as signed Paul A. Luthi  
pipe was pulled. (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3:00 PM Day: 22 Month: 9 Year: 1983

ACTUAL PLUGGING REPORT This well was plugged as ordered  
in above paragraphs.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 28 1983  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: The perforations were @ 5532' to 36'. They  
recovered 4460' of 4" pipe

I hereby certify that the above plugging instructions were given as herein stated  
and that I did / ~~did not~~ observe this plugging.

INVOICED

DATE 10-10-83  
INV. NO. 5688-6

Signed Paul A. Luthi  
(TECHNICIAN)