

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-193-20488-00-00  
Spot: E2SWSWNE Sec/Twnshp/Rge: 29-10S-32W  
2970 feet from S Section Line, 2200 feet from E Section Line  
Lease Name: BROECKELMAN Well #: 1  
County: THOMAS Total Vertical Depth: 4690 feet

Operator License No.: 32457  
Op Name: ABERCROMBIE ENERGY, LLC  
Address: 10209 W. CENTRAL, STE 2  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4687		250 SX
SURF	8.625	306		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/16/2015 10:30 AM  
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.  
Proposal Rcvd. from: JASON SCHULER Company: WILD WEST WELL SERVICE, INC. Phone: (620) 793-8186

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 600 # hulls.  
Shot perforations at 2516.  
Perfroations at 4174' - 4178', 4205' - 4210' and 4479' - 4488.  
DV Tool at 1819' w/300 sx cement

Plugging Proposal Received By: DARREL DIPMAN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/16/2015 2:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4400' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 3133' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1804' and pumped 130 sx cement. Good circulation of cement. Pulled tubing out and topped off casing w/15 sx full. Tied on to backside and squeezed w/15 sx cement. Shut in pressure 200 psi.

GPS: 39.15589 -100.91536

Perfs:

Top	Bot	Thru	Comments
4205	4210		
4174	4178		

Remarks: CONSOLIDATED CEMENT TICKET # 46590

Plugged through: TBG

MAR 04 2015 *CKM*

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

CM

KCC WICHITA

FEB 25 2015

RECEIVED

FEB 18 2015