

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-23148-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 2-14S-20W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: H LUEA Well #: A-1
County: ELLIS Total Vertical Depth: 3916 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3915		250 SX
SURF	8.625	250		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/27/2015 9:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR INC. Phone: (620) 275-2963

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 11 sx gel and 500 # hulls.
Perforations at 3872' - 3878'.
Alt II completion perforated at 1556' w/350 sx cement.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/27/2015 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service ran in hole with tubing to 3792'. Swift rigged to tubing, mixed and pumped 11 sx gel followed by 75 sx cement and 200 # hulls mixed in. Pulled tubing to 2100', mixed and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1100', mixed and pumped 90 sx cement w/50 # hulls to circulate cement to surface. Pulled tubing. Squeezed 5 1/2" casing w/20 sx cement at 300 psi. Shut in pressure 300 psi. Rigged to 8 5/8" surface casing and pumped 10 sx cement at 300 psi. Shut in pressure 300 psi.

GPS: 38.86977 -099.51118
4999' FSL 2279' FEL
SE NW NW NE

Perfs:

Top	Bot	Thru	Comments
3872	3878		


Remarks: SWIFT SERVICES TICKET # 26990

Plugged through: TBG

MAR 04 2015
AKM

District: 04

Signed _____



(TECHNICIAN)

CM

KCC WICHITA

FEB 25 2015

RECEIVED

FEB 13 2015