

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-01537-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 21-25S-4E  
4316 feet from S Section Line, 4373 feet from E Section Line  
Lease Name: CORFMAN Well #: 2  
County: BUTLER Total Vertical Depth: 2589 feet

Operator License No.: 33844  
Op Name: BLACK GOLD WELL SERVICE, INC.  
Address: 9868 NW PARALLEL RD  
TOWANDA, KS 67144

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2589		150 SX
SURF	8.625	123		100 SX CMT
SURF	8.625	125		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/30/2014 10:00 AM  
Plug Co. License No.: 34283 Plug Co. Name: WILLIS WELL SERVICE LLC  
Proposal Rcvd. from: JEREMY HURT Company: BLACK GOLD WELL SERVICE Phone: (316) 323-4734

Proposed Plugging Method: AS PER KCC RULES & REGS

KCC WICHITA  
MAR 02 2015  
RECEIVED

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/11/2015 9:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

WHEN RE-ENTERING WELL, SIGNIFICANT JUNK-IN-HOLE WAS ENCOUNTERED -- IT WAS DETERMINED THAT A BOTTOM PLUG WAS NOT FEASIBLE TO ATTEMPT DUE TO DETERIORATING CONDITIONS OF THE WELL. 1) RAN IN HOLE W/ TUBING TO APPROX. 270' WHERE HOLE WAS BRIDGED OFF (TUBING POSSIBLE OUTSIDE CASING). 2) PUMPED 25 SKS GEL AND 4 SKS OF HULLS THROUGH TUBING. 3) PUMPED APPROX. 35 SKS OF COMMON CEMENT W/ 2% CACL, RAN OUT OF HOLE W/ TUBING AND LET CEMENT SET FOR 1.5 HOURS. 4) RAN IN HOLE W/TUBING AND TAGGED CEMENT AT APPROX. 230'. 5) PUMPED APPROX. 90 SKS OF COMMON CEMENT W/ 2% CACL AND CIRCUALTED CEMENT TO SURRFACE. 2/11/2015. CEMENT FELL APPROX. 30'. TOPPED OFF WITH 5 SKS, CEMENTED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2587	2589	OH	

Remarks: CEMENTING COMPLETED BY ELITE ACID & CEMENTING, EUREKA KS. TICKET #2060. PLUGGED FOR COMPLIANCE W/ 82-3-111

Plugged through: TBG

MAR 04 2015ckm

District: 02

Signed Jonathan Hill  
(TECHNICIAN)