

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-22411-00-00
Spot: SENWNW Sec/Twnshp/Rge: 16-20S-11W
4290 feet from S Section Line, 4290 feet from E Section Line
Lease Name: SCHEUFLER Well #: 2
County: BARTON Total Vertical Depth: 3282 feet

Operator License No.: 4184
Op Name: CASINO PETROLEUM, LLC
Address: PO BOX 415
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3280		100 SX
SURF	8.625	248		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/09/2015 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: CHRIS BATCHMAN Company: CASINO PETROLEUM Phone: (620) 566-7111

Proposed Plugging Method: Rods in well at 1150'. Tubing in well at 2000'. Will plug from 1150'. Tried to fish rods and tubing stuck in well. Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/09/2015 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report: _____ Perfs: _____

Perforated at 1150', 510' and 220'. Ran tubing to 1148' and pumped 80 sx cement w/200 # hulls. Pulled tubing to 600'. Circulated cement to surface on casing and surface pipe w/170 sx cement and 200 # hulls. Pulled tubing and topped off w/40 sx cement. Maximum pressure 300 psi. Shut in pressure 100 psi.
GPS: 38.31629 -098.54983

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBC
CSG

MAR 04 2015 *CM*

District: 04

Signed Bruce Rodie
(TECHNICIAN) *CM*

FEB 12 2015

KCC WICHITA

FEB 25 2015

RECEIVED