

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20525-00-00  
Spot: SE Sec/Twnshp/Rge: 14-23S-41W  
1250 feet from S Section Line, 1250 feet from E Section Line  
Lease Name: WITT Well #: 2-14  
County: HAMILTON Total Vertical Depth: 2550 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2548	0	WITH 700 SX CMT
SURF	8.625	322		WITH 185 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/10/2015 1:00 PM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 935-7987

Proposed Plugging Method: FILL CASING WITH CMT FROM 2518' TO SURFACE WITH 165 SX CMT & 250# HULLS. CHECK BACKSIDE.

**KCC WICHITA**  
**MAR 02 2015**  
**RECEIVED**

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/10/2015 2:30 PM KCC Agent: KEN JEHLIK

**Actual Plugging Report:**

FILL 4 1/2" CASING WITH CMT FROM 2518' TO 0' USING 190 SX CMT & 200# HULLS. PRESSURE TO 400#. HOLDING. TOP OFF WITH 10 SX CMT. PUMP 90 SX CMT DOWN THE ANNULUS TO 250#.

**Perfs:**

Top	Bot	Thru	Comments
2508	2518		
2499	2504		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

**MAR 04 2015** *CKM*

District: 01

Signed *[Signature]*  
(TECHNICIAN)

RECEIVED  
FEB 13 2015  
KCC DODGE CITY *[Signature]*

*[Signature]*