

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-22761-00-00  
Spot: NWSWSWSW Sec/Twnshp/Rge: 6-14S-14W  
359 feet from S Section Line, 320 feet from W Section Line  
Lease Name: AMELIA Well #: D-04  
County: RUSSELL Total Vertical Depth: 3397 feet

Operator License No.: 3553  
Op Name: CITATION OIL & GAS CORP.  
Address: 14077 CUTTEN RD PO BOX 690688  
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3395		225 SX
SURF	8.625	476		380 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/12/2015 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: DENNIS Company: CITATION OIL AND GAS CORP Phone: (785) 639-6314

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 500 # hulls and 8 sx gel.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/12/2015 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

02/11/2015- Drilled out CIBP at 2730'.  
02/12/2015- Perforated at 1300', 915' and 300'. Ran tubing to 2700' and pumped 8 sx gel followed by 50 sx cement w/50 # hulls. Well circulated fluid out of backside. Pulled tubing to 1350' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 350' and pumped 85 sx cement. Cement circulated out backside. POOH. Hooked to casing and pumped 50 sx cement. Cement circulated out of the braden head. Shut in and pressured up to 200 psi. Shut in.

GPS: 38.85749 -098.92736

Remarks: ALLIED CEMENTING TICKET # 550066

Plugged through: TBG

MAR 04 2015 *CKM*

District: 04

Signed Ray A Dinkel

(TECHNICIAN)

CM

KCC WICHITA

FEB 18 2015

RECEIVED

Form CP-2/3

FEB 13 2015