

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-07244-00-00
Spot: SESENE Sec/Twnshp/Rge: 14-20S-11W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: BURCHART Well #: 1
County: BARTON Total Vertical Depth: 3291 feet

Operator License No.: 4871
Op Name: CURT'S OIL OPERATIONS LLC
Address: PO BOX 8
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3292		100 SX
SURF	8.625	222		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/15/2014 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CURT'S OIL OPERATIONS LLC Phone: (620) 793-2540

Proposed Plugging Method: Junk in well at 1320'.
Ordered 350 sx 60/40 pozmix 4% gel cement w/800 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/15/2014 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report: _____ Perfs: _____

Perforated at 1300' and 490'.
Ran tubing to 1250' and pumped 80 sx cement w/300 # hulls. Pulled tubing to 600', circulated cement to surface with 175 sx cement. Pulled tubing. Topped off with 60 sx cement. Cement circulated up surface pipe.
GPS: 38.31229 -098.49891

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

MAR 04 2015 *CKM*

District: 04

Signed Bruce Rodie
(TECHNICIAN) *CM*

KCC WICHITA

FEB 18 2015

RECEIVED

DEC 27 2014